

BELLEVUE-BILTMORE HOTEL
BELLEVUE FLORIDA

Table with 22 columns: WBS, Major, Minor, ITEM DESCRIPTIONS, QNTY, UNIT MSR, UNIT \$ MATERIAL, PRODUCTIVITY, UNIT/ TIME, CREW, ADJ. \$ HOURLY, UNIT \$ LABOR, UNIT \$ EQUIP, UNIT \$ SUB-CON, UNIT \$ OTHER, TOTAL MATERIAL, TOTAL.. MANHOURS, TOTAL LABOR, TOTAL EQUIPMENT, TOTAL SUB-CON, TOTAL OTHER TOTAL, COST*, UNIT PRICE, TOTAL AMOUNT. Includes sections for FOUNDATION AND UNDERPINNING, FENCE AND GATES, and 3000 CONCRETE FORMWORK.

BELLEVUE-BILTMORE HOTEL
BELLEVUE FLORIDA

Table with 24 columns: WBS, Major/Minor, ITEM DESCRIPTIONS, QNTY, UNIT MSR, UNIT \$ MATERIAL, PRODUCTIVITY, UNIT/ TIME, CREW, ADJ. \$ HOURLY, UNIT \$ LABOR, UNIT \$ EQUIP, UNIT \$ SUB-CON, UNIT \$ OTHER, TOTAL MATERIAL, TOTAL.. MANHOURS, TOTAL LABOR, TOTAL EQUIPMENT, TOTAL SUB-CON, TOTAL OTHER TOTAL, COST*, UNIT PRICE, TOTAL AMOUNT. Rows include categories like SHORING, MISC, RESTEEL, and CONCRETE IN PLACE.

BELLEVUE-BILTMORE HOTEL
BELLEVUE FLORIDA

Table with columns: WBS, Major/Minor, ITEM DESCRIPTIONS, QNTY, UNIT MSR, UNIT \$ MATERIAL, PRODUCTIVITY, UNIT/ TIME, CREW, ADJ. \$ HOURLY, UNIT \$ LABOR, UNIT \$ EQUIP, UNIT \$ SUB-CON, UNIT \$ OTHER, TOTAL MATERIAL, TOTAL.. MANHOURS, TOTAL LABOR, TOTAL EQUIPMENT, TOTAL SUB-CON, TOTAL OTHER TOTAL COST*, UNIT PRICE, TOTAL AMOUNT

BELLEVUE-BILTMORE HOTEL
BELLEVUE FLORIDA

Table with columns: WBS, Major/Minor, ITEM DESCRIPTIONS, QNTY, UNIT MSR, UNIT \$ MATERIAL, PRODUCTIVITY, UNIT/ TIME, CREW, ADJ. \$ HOURLY, UNIT \$ LABOR, UNIT \$ EQUIP, UNIT \$ SUB-CON, UNIT \$ OTHER, TOTAL MATERIAL, TOTAL.. MANHOURS, TOTAL LABOR, TOTAL EQUIPMENT, TOTAL SUB-CON, TOTAL OTHER, TOTAL COST*, UNIT PRICE, TOTAL AMOUNT.

BELLEVUE-BILTMORE HOTEL
BELLEVUE FLORIDA

WBS	Major	Minor	ITEM DESCRIPTIONS	QNTY	UNIT MSR	UNIT \$ MATERIAL	PRODUCTIVITY	UNIT/ TIME	CREW	ADJ. \$ HOURLY	UNIT \$ LABOR	UNIT \$ EQUIP	UNIT \$ SUB-CON	UNIT \$ OTHER	TOTAL MATERIAL	TOTAL.. MANHOURS	TOTAL LABOR	TOTAL EQUIPMENT	TOTAL SUB-CON	TOTAL OTHER	TOTAL COST*	UNIT PRICE	TOTAL AMOUNT	
			assume 25% additional protection of interstitial spaces	98,677.00	sqft						-		1.89		-		-	-	186,499.53	-	186,499.53	2.08	205,149.48	
			EXISTING FP DEMO								-				-		-	-	-	-	-	-	-	
			demo existing piping @ main hotel	1.00	lsum						-		45,000.00		-		-	-	45,000.00	-	45,000.00	49,500.00	49,500.00	
			* fire protection area *	493,385.00	sqft						-				-		-	-	-	-	-	-	-	
			*no. of plumbing fixtures *	1,503.00	each						-				-		-	-	-	-	-	-	-	
			FIXTURES								-				-		-	-	-	-	-	-	-	
			water closet	312.00	each						-				-		-	-	-	-	-	-	-	
			water closet	34.00	each						-				-		-	-	-	-	-	-	-	
			urinal	13.00	each						-				-		-	-	-	-	-	-	-	
			lavatory	353.00	each						-				-		-	-	-	-	-	-	-	
			lavatory	135.00	each						-				-		-	-	-	-	-	-	-	
			janitor's sink	2.00	each						-				-		-	-	-	-	-	-	-	
			mop sink	11.00	each						-				-		-	-	-	-	-	-	-	
			mop sink	3.00	each						-				-		-	-	-	-	-	-	-	
			wet bars	12.00	each						-				-		-	-	-	-	-	-	-	
			wet bars	2.00	each						-				-		-	-	-	-	-	-	-	
			wet bars	3.00	each						-				-		-	-	-	-	-	-	-	
			showers	161.00	each						-				-		-	-	-	-	-	-	-	
			showers	105.00	each						-				-		-	-	-	-	-	-	-	
			bathtub	254.00	each						-				-		-	-	-	-	-	-	-	
			bathtub	34.00	each						-				-		-	-	-	-	-	-	-	
			electric drinking fountain	9.00	each						-		2,000.00		-		-	-	18,000.00	-	18,000.00	2,200.00	19,800.00	
			emergency eyewash	2.00	each						-		1,450.00		-		-	-	2,900.00	-	2,900.00	1,595.00	3,190.00	
			15420.500 storm water distribution (drains@ flat roofs)	6,872.00	sqft						-		1.20		-		-	-	8,246.40	-	8,246.40	1.32	9,071.04	
			HVAC								-				-		-	-	-	-	-	-	-	
			15709.801 hvac main hotel	394,708.00	sqft						-		19.50		-		-	-	7,696,806.00	-	7,696,806.00	21.45	8,466,486.60	
			SUBTOTAL AMOUNT								-				-		-	-	13,799,130.33	-	13,799,130.33	15,179,043.36	15,179,043.36	
			16000 ELECTRICAL	1.00	LSUM						-				-		-	-	-	-	-	-	-	
			supply/install new electrical	394,708.00	sqft						-		17.46		-		-	-	6,891,601.68	-	6,891,601.68	19.21	7,580,761.85	
			lightning protection allowance @ main hotel	52,834.00	sqft						-		0.30		-		-	-	15,850.20	-	15,850.20	0.33	17,435.22	
			SUBTOTAL AMOUNT								-				-		-	-	6,907,451.88	-	6,907,451.88	7,598,197.07	7,598,197.07	
				394,708.00	sqft						-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
											-				-		-	-	-	-	-	-	-	
																				144,330,556.10				
OF ESTIMATE \$ 82,662,790.72																								

NO. EXCLUSIONS & QUALIFICATIONS

END